

| Item No | Unit | Quantity | Rate | Amount |
|--|------|----------|------|--------|
| <p><u>BILL NO.1</u></p> <p><u>PRELIMINARIES</u></p> <p>Preliminaries and General and Contract Data EC</p> <p><u>SECTION A: MINOR WORKS AGREEMENT- JBCC SERIES 2000</u></p> <p><u>Notes:</u></p> <p>The agreement is to be the JBCC series 2000 minor works Agreement prepared by the Joint Building Contracts Committee, August 2007 edition.</p> <p>The JBCC Minor Works Agreement Contract Data EC and the JBCC Minor Works Agreement Contract Data CE form an integral part of this agreement</p> <p>The ASAQS preliminaries (November 2007 edition) published by the Association of South African Quantity Surveyors for use with the said JBCC principal Building Agreement shall be deemed to be incorporated in these bills of quantities.</p> <p>Contractors are referred to the above mentioned documents for the intent and meaning of each clause thereof</p> <p>These clauses are hereinafter referred to by clause number and heading only. Where standard clauses or alternatives are not entirely applicable to this agreement such modifications, corrections or supplements as will apply are given under each relevant clause heading and such modifications, corrections or supplements shall take precedence notwithstanding anything contrary contained in the above mentioned documents.</p> <p>Where an item is not relevant to this specific contract such items are marked N/A (signifying "not applicable")</p> | | | | |
| <p>Carried Forward</p> <p>Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19</p> | | | R | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | |
|--|--|--------------------------------------|--|
| <p style="text-align: right;">Brought Forward</p> | | <p style="text-align: center;">R</p> | |
| <p><u>PREAMBLES FOR TRADES</u></p> | | | |
| <p>The Model of Preambles for trades(2008 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said Model Preambles will be entertained.</p> | | | |
| <p>Supplementary preambles are incorporated in these bills of quantities to satisfy the requirements of this project. Such supplementary preambles shall take precedence over the provisions of the said Model Preambles.</p> | | | |
| <p>The contractor's prices for all items throughout these bills of quantities must take account of and include for all of the obligations, requirements and specifications given in the said Model preambles and in any supplementary preambles.</p> | | | |
| <p><u>PRICING OF PRELIMINARIES</u></p> | | | |
| <p>Should the contractor select Option A in terms of subclause 3.2.1 in the Contract Data- Contractor to Employer (CE) for the purpose of adjustment of these preliminaries, the amount entered into the amount column in these preliminaries is to be divided into one or more of the three categories provided namely Fixed (F), Value related (V) and Time related (T).</p> | | | |
| <p><u>Pre- Tender and Post-Tender information is in the contract variables, schedule.</u></p> | | | |
| <p style="text-align: center;">-----</p> | | | |
| <p style="text-align: right;">Carried Forward</p> | | <p style="text-align: center;">R</p> | |
| <p>Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19</p> | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|---|---|------|--|---|--|
| Brought Forward | | | | R | |
| <u>SECTION A: PRINCIPAL BUILDING AGREEMENT</u> | | | | | |
| <u>Definitions (A1)</u> | | | | | |
| 1 | Definitions and interpretation (clause 1) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| <u>Objective and Preparation (A2)</u> | | | | | |
| 2 | Offer acceptance and performance (clause 2) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| <u>Preparation (A3-A14)</u> | | | | | |
| 3 | Documents (clause 3) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 4 | Design responsibility (clause 4) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 5 | Employer's agents (clause 5) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 6 | Site representative (clause 6) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| Carried Forward | | | | R | |
| Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | | | |

SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON STREET BLOEMFONTEIN

| | | | | |
|---|--|------|---|--|
| | Brought Forward | | R | |
| 7 | Compliance with regulations (clause 7) F:..... V:..... T:..... | Item | | |
| 8 | Works risk (clause 8) F:..... V:..... T:..... | Item | | |
| 9 | Indemnities (clause 9) F:..... V:..... T:..... | Item | | |
| 10 | General insurances (clause 10) F:..... V:..... T:..... | Item | | |
| 11 | Special insurances (clause 11) F:..... V:..... T:..... | Item | | |
| 12 | Effecting insurance (clause 12) F:..... V:..... T:..... | Item | | |
| 13 | Assignment (clause 13) F:..... V:..... T:..... | Item | | |
| | Carried Forward | | R | |
| Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | | |
|----|---|------------------------|------|--|---|--|
| | | Brought Forward | | | R | |
| 14 | Security (clause 14) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| | <u>Execution (A15-A23)</u> | | | | | |
| 15 | Preparation for and execution of the works (clause 15) fixed | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| 16 | Site and Access (clause 16) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| 17 | Contract instructions (clause 17) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| 18 | Setting out of the works (clause 18) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| 19 | Temporary works and Plant (clause 19) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| 20 | Nominated subcontractors (clause 20) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| | | Carried Forward | | | R | |
| | Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|----|---|------|--|---|--|
| | Brought Forward | | | R | |
| 21 | Selected subcontractors (clause 21) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 22 | Employer's Direct Contractors (clause 22) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 23 | Contractor's Domestic Sub-Contractors (Clause 23) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 24 | Allow for overtime | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | <u>Completion (A24-A30)</u> | | | | |
| 25 | Practical completion (clause 24) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 26 | Works completion (clause 25) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 27 | Final completion (clause 26) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | Carried Forward | | | R | |
| | Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|----|---|------|--|---|--|
| | Brought Forward | | | R | |
| 28 | Latent defects liability period (clause 27) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 29 | Sectional completion (clause 28) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 30 | Revision of date of practical completion (clause 29) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 31 | Penalty for non-completion (clause 30) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | <u>Payment (A31 - A35)</u> | | | | |
| 32 | Interim payment to the contractor (clause 31) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 33 | Adjustment to the contract value (clause 32) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 34 | Recovery of expense and loss (clause 33) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | Carried Forward | | | R | |
| | Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|----|---|------|--|---|--|
| | Brought Forward | | | R | |
| 35 | Final account and final payment (clause 34) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 36 | Payment to other parties (clause 35) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | <u>Cancellation (A36-A39)</u> | | | | |
| 37 | Cancellation by employer - contractor's default (clause 36) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 38 | Cancellation by employer - loss and damage (clause 37) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 39 | Cancellation by contractor - employer's default (clause 38) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 40 | Cancellation - cessation of the works (clause 39) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | <u>Dispute (A40)</u> | | | | |
| 41 | Settlement of Disputes (clause 40) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | Carried Forward | | | R | |
| | Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | |
|--|------|-----------------|---|
| | | Brought Forward | R |
| <u>Contract variables (A41)</u> | | | |
| <u>THE SCHEDULE</u> | | | |
| Information necessary for completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder | | | |
| 42 Pre-tender information (clause 41) | | | |
| F:..... V:..... T:..... | Item | | |
| <u>41.1 CONTRACTING AND OTHER PARTIES</u> | | | |
| 41.1.1 | | | |
| Employer: | | | |
| South African Revenue Service (SARS) | | | |
| Postal address: | | | |
| Linton House Ground floor, 570 Fehrsen Street | | | |
| .Pretoria..... | | | |
| Code | | | |
| Tel | | | |
| Fax | | | |
| E-mail | | | |
| Physical Address: | | | |
| | | | |
| | | | |
| | | Carried Forward | R |
| Section No. 1 | | | |
| Section 1 | | | |
| Bill No. 1 | | | |
| Preliminaries | | | |
| Provisional Bills of Quantities | | | |
| Proposal 19 | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | |
|---|--|--|---|--|
| Brought Forward | | | R | |
| 41.1.2 Principal Agent: South African Revenue Service (SARS) Postal address: Linton House Ground floor, 570 Fehrsen Street Pretoria Code Tel: Fax: Contact Person: Cell: E-mail: | | | | |
| 41.1.3 Agents service:Architect Agent South African Revenue Service (SARS) Postal address: Linton House Ground floor, 570 Fehrsen Street Pretoria Tel: Fax: E-mail: Contact Person: | | | | |
| Carried Forward Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | R | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | |
|---|--|--|---|--|
| Brought Forward | | | R | |
| <p>41.1.4</p> <p>Agents service: Quantity Surveyor</p> <p>Agent</p> <p>South African Revenue Service (SARS)</p> <p>.....</p> <p>Postal address:</p> <p>Linton House Ground floor, 570 Fehrsen Street</p> <p>.....</p> <p>Pretoria.....</p> <p>Code</p> <p>Tel:</p> <p>Fax:</p> <p>Contact Person:</p> <p>E-mail:</p> <p>Cell Number:</p> <p>41.2 CONTRACT DETAILS</p> <p>41.2.1 Works Description:</p> <p>Proposed Supplying and Installations of Shopfitting in Bloemfontein SARS Office.</p> <p>41.2.2 Site Description:</p> <p>88 Zastron street Bloemfontein</p> | | | | |
| Carried Forward | | | R | |
| <p>Section No. 1</p> <p>Section 1</p> <p>Bill No. 1</p> <p>Preliminaries</p> <p>Provisional Bills of Quantities</p> <p>Proposal 19</p> | | | | |

SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON STREET BLOEMFONTEIN

| | | |
|--|--|---|
| <p align="center">Brought Forward</p> | | R |
| <p>41.2.3 Work or installations by direct contractors:</p> <p>Construction work Electrical Work Mechanical Work Furniture Installation</p> | | |
| <p>41.2.4 This agreement is for a government contract:</p> <p align="right">Yes</p> | | |
| <p>41.2.5 Date on which possession of the site is intended to be given:</p> <p align="right">26 April 2018</p> | | |
| <p>41.2.6 Period for the commencement of the works after the contractor takes possession of the site</p> <p align="right">2 (Two) <i>working days</i></p> | | |
| <p>41.2.7 Intended date of practical completion and the penalty per calendar day for the works as a whole</p> <p align="right">01 June 2018</p> <p align="right">R./day....5 000..... <i>Penalty Amount</i></p> | | |
| <p align="center">Carried Forward</p> | | R |
| <p>Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19</p> | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | |
|--|--|--|---|--|
| <p style="text-align: right;">Brought Forward</p> | | | R | |
| <p>41.2.8 Intended date of practical completion and the penalty per calendar day for the works in sections:</p> | | | | |
| <p style="text-align: right;">Section 1</p> <p>.....N/A.....</p> | | | | |
| <p>R.....N/A..... <i>Penalty Amount</i></p> | | | | |
| <p style="text-align: right;">Section 2</p> <p>.....N/A..... <i>Date</i></p> | | | | |
| <p>R.....N/A..... <i>Penalty Amount</i></p> | | | | |
| <p style="text-align: right;">Section 3</p> <p>.....N/A..... <i>Date</i></p> | | | | |
| <p>R.....N/A..... <i>Penalty Amount</i></p> | | | | |
| <p style="text-align: right;">Section 4</p> <p>.....N/A..... <i>Date</i></p> | | | | |
| <p>R.....N/A..... <i>Penalty Amount</i></p> | | | | |
| <p>41.2.9 The law applicable to this agreement shall be that of</p> <p style="text-align: right;">South African Law</p> | | | | |
| <p>41.3 INSURANCES</p> | | | | |
| <p>41.3.1 Contract works insurance to be effected by:</p> <p style="text-align: right;"><i>Contractor:</i></p> <p style="text-align: right;"><i>For the Sum of R1 .2 Million.....</i></p> | | | | |
| <p>41.3.2 Supplementary insurance is required</p> <p style="text-align: right;"><i>No</i></p> | | | | |
| <p style="text-align: right;">Carried Forward</p> <p>Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19</p> | | | R | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | |
|--|--|---|--|
| <p style="text-align: right;">Brought Forward</p> | | R | |
| <p>41.3.3 Public liability insurance to be effected by: <i>Contractor:</i> <i>For the Sum of R.....</i></p> | | | |
| <p>41.4 DOCUMENTS</p> | | | |
| <p>41.4.1 Waivers of contractors lien or right of continuing possession is required <p style="text-align: right;">Yes</p></p> | | | |
| <p>41.4.2 Number of construction document copies to be supplied to the contractor free of charge: <p style="text-align: right;">3 <i>Number of</i></p></p> | | | |
| <p>41.4.3 Bills of Quantities/Lump sum document schedule of rates drawn up in accordance with: Standard System of Measurement</p> | | | |
| <p>41.4.4 On acceptance of the tender the bills of quantities/lump sum document is to be submitted within working days N/A</p> | | | |
| <p>41.4.5 JBCC building work are to be included in the contract documents: <p style="text-align: right;">Yes</p></p> | | | |
| <p>41.4.6 The contract value is to be adjusted using escalation adjustment indices <p style="text-align: right;">No</p></p> | | | |
| <p style="text-align: right;">Carried Forward</p> <p>Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19</p> | | R | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | |
|--|--|--|-------------------------------------|--|
| <p style="text-align: right;">Brought Forward</p> | | | <p style="text-align: right;">R</p> | |
| <p>41.4.7 Details of changes made to the provision of JBCC standard documentation: <i>[An addendum is to be attached should the space provided be insufficient]</i></p> <p>.....</p> <p>.....</p> <p>.....</p> <p>.....</p> <p>.....</p> | | | | |
| <p style="text-align: right;">Carried Forward</p> <p>Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19</p> | | | <p style="text-align: right;">R</p> | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|----|---|------|--|---|--|
| | Brought Forward | | | R | |
| | <u>SECTION B: PRELIMINARIES</u> | | | | |
| | <u>Definition and interpretation (B1)</u> | | | | |
| 43 | Definition and interpretation (Clause 1.0) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | <u>Documents (B2)</u> | | | | |
| 44 | Checking of documents (Clause 2.1) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 45 | Provisional bills of quantities (Clause 2.2) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 46 | Availability of construction documentation (Clause 2.3) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | <u>Previous work and adjoining properties (B3)</u> | | | | |
| 47 | Previous work - dimensional accuracy (Clause 3.1) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 48 | Previous work - defects (Clause 3.2) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | Carried Forward | | | R | |
| | Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|----|--|------|--|---|--|
| | Brought Forward | | | R | |
| 49 | <p>Inspection of adjoining properties etc (Clause 3.3)</p> <p>F:..... V:..... T:.....</p> <p><u>Samples, shop drawings and manufacturer's instructions (B4)</u></p> | Item | | | |
| 50 | <p>Samples of materials (Clause 4.1)</p> <p>F:..... V:..... T:.....</p> | Item | | | |
| 51 | <p>Clause 4.1 is hereby amended by the addition of the following: The principal Agent may reject any materials or colours not corresponding with the approved samples. The approved samples shall be kept on site untill completion of the works.</p> <p>Should any materials or items specified prove to be either unavailble, in poor supply or likely to delay to the works, the contractor shall notify the principal agent in sufficient time for suitable alternatives to be considered. Any claims for delays resulting from the contractor not conforming with the terms of this clause will not be entertained or allowed</p> | Item | | | |
| 52 | <p>Workmanship samples (Clause 4.2)</p> <p>F:..... V:..... T:.....</p> | Item | | | |
| 53 | <p>Shop drawings (Clause 4.3)</p> <p>F:..... V:..... T:.....</p> | Item | | | |
| | Carried Forward | | | R | |
| | <p>Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19</p> | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | |
|----|---|------|---|--|
| | Brought Forward | | R | |
| 54 | Clause B4.3 is hereby amended by the addition of the following: General responsibilities Procedures | Item | | |
| 55 | Compliance with manufacturer's instructions (Clause 4.4) | Item | | |
| | <u>Deposit and Fees (B5)</u> | | | |
| 56 | Deposit and Fees (Clause 5.1) | Item | | |
| | <u>Temporary services (B6)</u> | | | |
| 57 | Water (Clause 6.1) | Item | | |
| 58 | Electricity (Clause 6.2) | Item | | |
| 59 | Telecommunication equipment (Clause 6.3) | Item | | |
| 60 | Ablution facilities (Clause 6.4) | Item | | |
| 61 | Main noticeboard (Clause 6.5) | Item | | |
| 62 | The contractor shall provide a main noticeboard of an approved design with the tittle of the project and the names of the employer, the principle agent, the agents and the contractor thereon. The principle agent shall instruct the contractor where the noticeboard is to be erected. | Item | | |
| | <u>Prime cost amount (B7)</u> | | | |
| 63 | Responsibility for prime cost amounts (Clause 7.1) | Item | | |
| | <u>Special attandance on n/s subcontractors (B8)</u> | | | |
| 64 | Special attandance (Clause 8.1) | Item | | |
| | Carried Forward | | R | |
| | Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|----|--|--|------|---|--|
| | Brought Forward | | | R | |
| | <u>General (B9)</u> | | | | |
| 65 | Protection of works (Clause 9.1) | | Item | | |
| 66 | Protection/isolation of existing/sectionally occupied works (Clause 9.2) | | Item | | |
| 67 | Security of the works (Clause 9.3) | | Item | | |
| 68 | Notice before covering work (Clause 9.4) | | Item | | |
| 69 | Disturbance (Clause 9.5) | | Item | | |
| 70 | Environmental disturbance (Clause 9.6) | | Item | | |
| 71 | Works cleaning and clearing (Clause 9.7) | | Item | | |
| 72 | Vermin (Clause 9.8) | | Item | | |
| 73 | Overhand work (Clause 9.9) | | Item | | |
| | Carried Forward | | | R | |
| | Section No. 1 | | | | |
| | Section 1 | | | | |
| | Bill No. 1 | | | | |
| | Preliminaries | | | | |
| | Provisional Bills of Quantities | | | | |
| | Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | | |
|----|---|------------------------|------|--|---|--|
| | | Brought Forward | | | R | |
| | <u>The site (B3)</u> | | | | | |
| 74 | Geotechnical investigation (B3.2) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| 75 | Inspection of the site (B3.3) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| 76 | Existing premises occupied (B3.4) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| 77 | Services - known (B3.7) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| 78 | Services - unknown (B3.8) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| 79 | Protection of trees etc (B3.9) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| 80 | Articles of value (B3.10) | | | | | |
| | F:..... V:..... T:..... | | Item | | | |
| | | Carried Forward | | | R | |
| | Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|----|---|------|--|---|--|
| | Brought Forward | | | R | |
| 81 | Management of the works (B4.1) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 82 | Programming for the works (B4.2) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 83 | Progress meetings (B4.3) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 84 | Technical meetings (B4.4) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 85 | Workmanship samples (B5.2) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 86 | Shop drawings (B5.3) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | <u>Temporary works and plant (B6)</u> | | | | |
| 87 | Enclosure of the works (B6.2) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | Carried Forward | | | R | |
| | Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|----|---|------|--|---|--|
| | Brought Forward | | | R | |
| 88 | Advertising (B6.3) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 89 | Plant, equipment, sheds and offices (B6.4) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 90 | Subcontractors notice board (B6.6) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | <u>Attendance on N/S Subcontractors ()</u> | | | | |
| 91 | General attendance (B9.1) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 92 | Special attendance (B9.2) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 93 | Commissioning - Fuel, water and power (B9.3) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | Carried Forward | | | R | |
| | Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|-----|---|------|--|---|--|
| | Brought Forward | | | R | |
| | <u>Financial aspects (B10)</u> | | | | |
| | Statutory taxes, duties and levies (B10.1) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 94 | Payment of preliminaries (B10.2) Alternative ? shall apply | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 95 | Adjustment of preliminaries (B10.3) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 96 | Payment certificate cash flow (B10.4) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| 97 | Contractor information supply (B10.5) | | | | |
| | F:..... V:..... T:..... | Item | | | |
| | <u>Schedule of variables</u> | | | | |
| 98 | The pre-tender and post-tender information is stated in the variables | Item | | | |
| | <u>SECTION C: SPECIFIC PRELIMINARIES</u> | | | | |
| 99 | Standard conditions of tender | Item | | | |
| 100 | Specific conditions of tender | Item | | | |
| 101 | Tender data schedule | Item | | | |
| | Carried Forward | | | R | |
| | Section No. 1 Section 1 Bill No. 1 Preliminaries Provisional Bills of Quantities Proposal 19 | | | | |

SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON STREET BLOEMFONTEIN

[illegible]

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| Item No | | Unit | Quantity | Rate | Amount |
|---------|--|------|----------|------|--------|
| | <u>WET KITCHEN (SF-05-KTC-WET-1 REV.12)</u> | | | | |
| | <u>Counter Top</u> | | | | |
| 1 | 600mm deep x 30mm thick Rustenburg black granite counter top. Top and bottom bullnose front edge. | No | 4 | | |
| | <u>Cupboard Units</u> | | | | |
| 2 | Wall hung: 900mm wide x 616mm high x 2262mm deep carcass from white grade A Melamine. Vancouver maple door facing edge strips. Side of carcass facing hydroboil from 16mm thick Vancouver maple (Colour code 688) PG Bison Melawood Board. Cupboard doors from 16mm thick Vancouver Maple (Colour code 688) PG Bison Melawood board with 2.5mm matching high impact PVC edging strips. Fitted with 16mm shelves and 2 no Roco iris handles (E0136BM-Matt black). Securely mounted to back panel. As per specification drawing. | No | 4 | | |
| 3 | Single Unit: 450mm wide x 768mm high x 560mm deep carcass from white grade A Melamine. Vancouver Maple door facing edge strips. On pedestal foot planed for level installation. Cupboard doors from 16mm thick Vancouver Maple (Colour code 668) PG Bison Melawood board with 2.5mm matching high impact PVC edging strips. Fitted with 2x 16mm shelves with door hinges and 1 no Roco Iris handles (E0136) BM-Matt Black), 1 no. 25mm Cam lock with 45mm cranked cam barrel 19x25mm code VLC925CNP nickel. Hinge and handle location as per drawing. | No | 4 | | |
| 4 | Sink Unit: 900mm wide x 768mm high x 560mm deep carcass from white grade A Melamine. Vancouver Maple door facing edge strips. On pedestal foot planed for level installation. Cupboard doors from 16mm thick Vancouver Maple (Colour code 688) PG Bison Melawood board with 2.5mm matching high impact PVC edging strips. No shelves. Fitted with door hinges and 2 no Roco Iris handles (E0136) BM-Matt Black), 2 no. 25mm Cam lock with 45mm cracked cam barrel 19x25mm code VLC925CNP nickel as per specification drawing. | No | 4 | | |
| | Carried Forward | | | R | |
| | Section No. 2 Section 2 Bill No. 1 Shopfittings Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|---|--|----|---|---|--|
| | Brought Forward | | | R | |
| 5 | Drawer unit: 450mm wide x 768mm high x 560mm deep carcass from white grade A Melamine.Vancouver Maple door facing edge strips. On pedestal foot planed for level installation. 4 drawer fronts from 16mm thick Vancouver Maple (Colour code 688) PG Bison Melawood board with 2.5mm matching high impact PVC edging strips. Drawer boxes from white Melamine faced 16mm high density grade A chipboard. 13.5mm gap between box and each carcass side. 4 no. Gelmar 500mm x 35mm Full Extension Telescopic Ball Bearing Sde Mounted (Code 7053). Fitted with 4 No Roco Iris handles fronts (E0136 BM-Matt Black). Gap spacing between drawer units matching and exact. Handle location as per specification drawing. | No | 4 | | |
| | Paneling | | | | |
| 6 | Side Panel: 600 x 3000 x 16mm thick Vancouver maple (Colour code 688) PG Bison Melawood board. 2.5mm high impact matching maple edging. Board installed grain vertical as per specification drawing. | No | 8 | | |
| 7 | Back Panel: 2971mm long x 3000 mm high x 16mm thick high density grade A chipboard cladded one side with Vancouver Maple (Colour code 688) Formica laminate. Board installed grain vertical. Board joint from 10mm aluminium flush fitted U- channel to C/L of width as per drawing. | No | 4 | | |
| 8 | Horizontal Bulkhead panel: 2971mm x 600mm deep x 22mm thick high density grade A particle board cladded both sides with Vancouver Maple (Colour code 688) Formica laminate. Front edging from 22mm wide 2.5mm thick high impact matching maple PVC edging strip. Aluminium insets as per drawing. | No | 4 | | |
| 9 | Vertical edge panel: 2987mm wide x 1800mm long x 22mm thick high density grade A chipboard board cladded both sides with Vancouver Maple (Colour code 688) Formica laminate. Board installed grain vertical. 2.5mm thick high impact matching 22mm wide maple PVC edging as per specification drawing. | No | 4 | | |
| | Carried Forward | | | R | |
| | Section No. 2 Section 2 Bill No. 1 Shopfittings Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|----|--|----|----|---|--|
| | Brought Forward | | | R | |
| 10 | Shelves: 683mm x 600mm deep x 16mm thick Vancouver Maple (Colour code 688) PG Bison Melawood board. 2.5mm high impact Maple edging. Shelves installed with non height adjustable PVC cleats as per drawing. | No | 8 | | |
| | Skirting | | | | |
| 11 | 75mm natural anodised aluminium skirting glued to drywall, kick plate and vertical boards with contact adhesive solvent free. | m | 16 | | |
| | PLUMBING AND DRAINAGE | | | | |
| | Note: Tenderers are advised to study notes to bidders and Model of Preambles before pricing this bills of quantities. | | | | |
| | SANITARY FITTINGS | | | | |
| | Zink | | | | |
| 12 | Franke:Range quinline QLX621-110, 1 and 1/2 type drop in reversible stainless steel satin finish, product code: 820006 and size is 1100mm x 500mm as per specification drawing. | No | 4 | | |
| | ELECTRIC WATER HEATERS | | | | |
| | Zip hydroboil | | | | |
| 13 | 7.5L hydroboil with and including isolator switch, Zip triple action under sink filter for purification and overflow/drip pipe. Unit to have brushed stainless steel finish and boiling water warning sticker. | No | 4 | | |
| 14 | Hydroboil isolator and hookup. | No | 4 | | |
| | 'P' trap | | | | |
| 15 | Franke Spazio F/2 Plumbing Kit for Franke 2 bowl Sink. Product Code 301251. | No | 4 | | |
| | Carried Forward | | | R | |
| | Section No. 2 Section 2 Bill No. 1 Shopfittings Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|----|---|----|------|---|--|
| | Brought Forward | | | R | |
| | <u>Geyser</u> | | | | |
| 16 | Kwikhot PRX-10 UB 10L under counter geyser to be supplied and fitted by shopfitter. Shut off valves, expansion valves and master flow valves and isolator plug must be included as part of shopfitters scope. | No | 4 | | |
| 17 | Geyser power and hookup. | No | 4 | | |
| | <u>Tap</u> | | | | |
| 18 | Grohe: Eurosmart chrome, code: 33281 single lever mixer 1/2". | No | 4 | | |
| | <u>BUDGETARY ALLOWANCE</u> | | | | |
| 19 | Budgetary Allowance of R 20 000.00 (Twenty Thousand Rand) NETT, for water supply to be used as directed by the Principal Agent and to be deducted in whole or in part if not required. | | Item | | |
| | <u>Electrical</u> | | | | |
| 20 | Extra over plugs fitment, wiring and testing. | No | 12 | | |
| 21 | Allow for Electrical Certificate of Compliance. | | Item | | |
| 22 | Supply and fitment down light fittings in the kitchen Bulkhead SARS lighting Led-01-7D. | No | 12 | | |
| | <u>Testing</u> | | | | |
| 23 | Allow for Plumbing Certificate of Compliance. | | Item | | |
| | <u>RECEPTION SF-01-RECEP-3 (Rev. 4)</u> | | | | |
| 24 | 32mm Rustenburg black grade A granite writing top with 10mm rounded polished corner to edges, 5h x 5d mm shadow edge joint full length and steel plate fixed to top of round post and secured to granite. Granite down stand height 118mm to client facing side. Polished both sides. | No | 1 | | |
| | Carried Forward | | | R | |
| | Section No. 2 Section 2 Bill No. 1 Shopfittings Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|--|--|----|------|---|--|
| | Brought Forward | | | R | |
| 25 | 32mm thick Vancouver Maple CDL counter Top. Half round solid maple edge for finishing including Maple CDL vertical board, PG Bison, Formica Laminates, 32mm Vancouver Maple Formica (Code:688). 40mm Diameter mild steel post Satin Chrome finish, CDS Plastics CMS 03 Grommit with 75mm Brushed Natural anodized Aluminium. 10 x 10mm; 90 degree angle, 10 x 5mm; U- Channel and 16mm vancouver Maple 688 formica shelf with 2.5mm thick Maple PVC high impact edging including CDS plastics CMS03 Charcoal cable outlet for cable reticulation management. | No | 1 | | |
| | <u>SECURITY COUNTER (SF-02-SECURITY-3 REV 3)</u> | | | | |
| 26 | 32mm thick x 643 deep x 2400mm long Rustenburg black granite counter top with 15mm polished rounded edges approximately 750mm high, with 32mm Maple Melamine front - grain vertical, including 16mm Maple melamine shelf and upright and aluminium skirting and aluminium corner caps full height to every corner of all boxed out sections glued to counter.As per drawing specification. | No | 3 | | |
| | <u>SELF HELP DESK</u> | | | | |
| 27 | Aluminium adjustable levelling feet . | No | 7 | | |
| 28 | 22mm PG Bison board13 with 0.5 formica with overlay both sides - Vancouver Maple 688 finish grain vertical. As per specification drawing. | No | 1 | | |
| 29 | 32mm Rustenburg black grade A granite counter top with 8mm radius rounded polished corner to edges | No | 1 | | |
| 30 | Allow for accessories. | | Item | | |
| | <u>SCANNER TABLE(SF15-BO-SCAN-1 REV 1)</u> | | | | |
| 31 | Scanner table by metal detector. | No | 2 | | |
| | Carried Forward | | | R | |
| Section No. 2 Section 2 Bill No. 1 Shopfittings Provisional Bills of Quantities Proposal 19 | | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|--|---|----|----|---|--|
| Brought Forward | | | | R | |
| <u>AGENT COUNTERS (SF-03-AGENTS-1 REV 14)</u> | | | | | |
| 32 | Horizontal work top: Bison 32mm formica 0.8 Laminate, colour: Vancouver Maple, code :688 and Top Surface Insert formica 0.8 laminate Colour. Formica 0.2 balanced brown backer (roll) and all cut outs and joints must be sealed with double coating external Grade Poly Urethane clear vanish including CNS plastics CMS03 80mm charcoal PC Grommit and CNC router cut board profiles. Board type as per drawing specification. | No | 32 | | |
| 33 | Vertical Full Height Separator Panel: From 2 Vancouver Maple Grade A high density Melawood boards (Colour Code 688) with spacer blocks to create 90mm when put together with 90mm aluminium drywall end caps on each vertical face. Panel size 1500mm wide x 2400mm high. All exposed board cuts to receive 2 coats external grade poly urethane sealer. Slots for cable and power reticulation as required. As per specification drawing. | No | 2 | | |
| 34 | Glass Support Separator Panel: From 2 Vancouver Maple Grade A high density Melawood boards (Colour Code 688) with spacer blocks to create 76mm when put together with 76mm aluminium drywall end caps on each vertical face. Panel size 1500mm wide x 720mm high. All exposed board cuts to receive 2 coats external grade poly urethane sealer. Slots for cable and power reticulation as required. As per specification drawing. | No | 15 | | |
| 35 | End Unit Panel: Vancouver Maple Grade A high density Melawood board (Colour Code 688) size 1500mm wide x 3000mm high with matching 2.5mm high impact PVC edging trim. Slots for cable and power reticulation as required. As per specification drawing. | No | 15 | | |
| 36 | Drawer door with horizontal Roco Iris handles and locks Code RE0136MB including Roco runner 300x45 RTS611 ball runner . As per drawing specification. | No | 2 | | |
| Carried Forward | | | | R | |
| Section No. 2 Section 2 Bill No. 1 Shopfittings Provisional Bills of Quantities Proposal 19 | | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|----|--|----|------|---|--|
| | Brought Forward | | | R | |
| 37 | Vancouver Maple Melamine with 3mm PVC edging strip to all edges. | | Item | | |
| 38 | 32mm x 1500 x 688mm Vancouver Maple formica front facade . | No | 32 | | |
| 39 | 76 x 25mm aluminium U channel end capping glued in place. | No | 15 | | |
| 40 | 100mm wide x 45mm high x 1774mm long solid Maple timber section with clear varnish (Satin) Varnish finish and 15mm radius corner to edge of solid Maple section on sides and ends with slot to receive glass. | No | 18 | | |
| 41 | Supawood bulkhead not exceeding 600mm as per drawing specifications (contractor must measure ceiling height prior to manufacture). Bulkhead must be hung from concrete soffit. Bulkhead may not rest on vertical panels. | m | 56 | | |
| 42 | Extra over for CPU brackets manufactured and fitment underside of counter (code:PC-FB-01- Metal) . | No | 64 | | |
| | <u>Skirting</u> | | | | |
| 43 | 75mm natural anodised aluminium skirting glued to supawood, kick plate and vertical boards with contact adhesive solvent free. | m | 94 | | |
| | <u>Down lighters</u> | | | | |
| 44 | Supply and fitment down light fittings on the counters- SARS lighting Led-01-7D. | No | 32 | | |
| | <u>Glass</u> | | | | |
| 45 | 10mm x 1686mm wide x 1640mm high toughened safety glass panel with decorative sand blast vinyl and aluminium U channel ends caps. | No | 18 | | |
| | Carried Forward | | | R | |
| | Section No. 2 Section 2 Bill No. 1 Shopfittings Provisional Bills of Quantities Proposal 19 | | | | |

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| | | | | | |
|--|---|----|----|---|--|
| Brought Forward | | | | R | |
| <u>WRITING COUNTERS- (SF-04-WRITING-1 REV.5)</u> | | | | | |
| 46 | 32mm thick x 410mm deep x 1600mm long PG Bison Formica counter top (colour: Graphite Graphix) | No | 4 | | |
| 47 | 9mm Stainless Steel Rod to have concealed fixing and 6mm Rods as A4 dividers and 8mm pre drilled toughened glass. | No | 16 | | |
| 48 | 100mm wide x 1038mm boxed out section from 16mm Vancouver Maple Melawood with aluminium skirting. | No | 4 | | |
| 49 | 9mm superwood back panel with 0.8mm Vancouver Maple formica to front face. 2.5mm matching high impact PVC edging to sides and top. | No | 4 | | |
| <u>CATERING COUNTER (SF-UNIT A)</u> | | | | | |
| 50 | 32 mm thick x 600mm deep Rustenburg Black granite counter top. 5mm rounded polished edge to top and bottom front edge of counter | No | 1 | | |
| 51 | 32mm thick superwood for leg 1 | No | 1 | | |
| 52 | 32mm thick superwood for leg 2 | No | 4 | | |
| 53 | 22mm thick vancouver Maple Melawood panel. | No | 1 | | |
| 54 | Drawer unit: 450mm wide x 768mm high x 560mm deep carcass from white grade A Melamine.Vancouver Maple door facing edge strips. On pedestal foot planed for level installation. 4 drawer fronts from 16mm thick Vancouver Maple (Colour code 688) PG Bison Melawood board with 2.5mm matching high impact PVC edging strips. Drawer boxes from white Melamine faced 16mm high density grade A chipboard. 13.5mm gap between box and each carcass side. 4 no. Gelmar 500mm x 35mm Full Extension Telescopic Ball Bearing Side Mounted (Code 7053). Fitted with 4 No Roco Iris handles fronts (E0136 BM-Matt Black). Gap spacing between drawer units matching and exact. Handle location as per specification drawing. | No | 1 | | |
| Carried Forward | | | | R | |
| Section No. 2 Section 2 Bill No. 1 Shopfittings Provisional Bills of Quantities Proposal 19 | | | | | |

SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON STREET BLOEMFONTEIN

[illegible]

**SUPPLYING AND INSTALLATION OF SHOPFITTING FOR SARS ZASTRON
STREET BLOEMFONTEIN**

| <u>FINAL SUMMARY</u> | | Page No | Amount |
|--|----------------------------------|--------------------|---------------|
| Section No | | | |
| 1 | Section 1 | -24- | |
| 2 | Section 2 | -33- | |
| | SUB TOTAL | | R |
| <u>CONTINGENCY</u> | | | |
| | Allow 15% contingency. | Item | |
| | VALUE ADDED TAX | | R |
| | SUB TOTAL | | R |
| | Carried to Form of Tender | | R |
| Provisional Bills of Quantities Proposal 19 | | | |